

#### Presentation

- Introduction
- Project Overview (CAD #4, North Terminal Extension, Phase V Dredging)
- Brief History of Dredging and CAD Cells in the Harbor
- Project Benefits and Details

















# Project Overview






History of New Bedford / Fairhaven Harbor

# Superfund and State-Enhanced Remedy

- 1983: EPA declared more than
   18,000 acres of New Bedford Harbor
   and Buzzards Bay a Superfund site
- 1998: A Record of Decision (ROD) was issued
- State-Enhanced Remedy (SER)
   Provision of ROD
  - DEP = Lead Agency for SER
  - Statement of Work (SOW) 30 days for EPA consistency determination
  - Work Plan to be provided 60 days prior to beginning the Work




# State-Enhanced Remedy


- Dredge Projects Phase I IV
- CAD Cell Construction
- Interim Federal Channel Dredging



 Dredging of contaminated sediments that would otherwise remain in harbor




# Dredging Progress Through April 2019 by SER and US EPA (Superfund) 1.35 Million Cubic Yards Complete\*



- Lower Harbor/Upper Harbor to LHCC by US EPA Lower Harbor by MaDEP/NBHDC
- Upper Harbor offsite by US EPA

Shoreline with Offsite Disposal

# Confined Aquatic Disposal (CAD) Cells




For illustrative purposes only - NOT TO SCALE

# CAD Cell #4 Siting

- Siting Evaluation Based on:
  - Location within DMMP
  - Geotechnical Properties of the Site Location
  - Potential for Interference with Existing Navigational Uses
  - Interaction with Existing and Planned CAD Cells
  - Depth to Rock
  - Proximity to Existing Navigational Channels
  - Thickness of Mud Layer to be Placed in CAD #2
  - Need for Transitional CAD Cell
  - Need for Channel to Access CAD Cell Location
  - Proximity to Shoreline / Residences




# CAD Cell #4 Siting



#### CAD Cell #4

- Capacity for 500,000 cy of dredged sediments
- Includes 50,000 cy for USACE top of CAD cell materials and 30,000 cy contingency
- Includes access channel / improves navigation
- Sediments to be placed in CAD Cell #4:
  - ✓ Significantly lower PCB concentrations compared to surface sediments in surrounding area
  - ✓ Lower levels of PCBs than in EPA CAD Cells






#### CAD Cell #4

- Construction Sequence:
  - Surface contaminated sediment dredged from footprint of CAD will be placed into an ex. CAD cell
  - Clean material that is dredged during construction of the CAD cell and that is not geotechnically suitable as backfill for the North Terminal will be disposed of at either the Cape Cod Bay Disposal site or the Rhode Island Sound disposal



#### North Terminal Extension

- Total Extension = 1,825 LF of bulkhead /commercial berth space
- Expanded Terminal Area = 484,000 SF
  - North Terminal, Future Extension, Seatrade
- BUILD Grant for \$15.4 M



## North Terminal Extension




# Phase V Dredging

- Dredging
  - Commercial industries
  - Marinas
  - Public infrastructure
  - Residential properties
- Activating Underutilized Waterfront
- Economic Benefits
  - 879 new jobs created
  - \$69.4 million in annual wages/respending/local consumption
  - \$286 million in business revenue
  - \$12.5 million in state/local taxes
- Navigation
- Enhanced Clean Up for Harbor
  - 420,000 CY +/- and 3,475,401 SF +/-




# Phase V Dredging

- 47 Sites= Total number of properties participating in Phase V
- 25 Sites = Number of Fairhaven
   properties (12 commercial properties,
   13 residential properties)
- 22 Sites = Number of NB properties
- 420,000 CY =Total volume of Phase V dredging with CAD cell disposal
- 192,000 CY from Fairhaven sites/businesses (46% of Phase V dredging)
- 228,000 CY from New Bedford sites/businesses (54% of Phase V dredging)






#### Cooke Island Realty LLC






#### North East Maritime







#### Seaport Inn







Coast Guard Auxiliary






Town of Fairhaven Pease Park






Blue Harbor Seafood






Harbor Hydraulics






#### Fairhaven Shipyard North






Town of Fairhaven
Union Wharf







#### WJA Properties






Steamship Authority









#### **Bayline Boats**










Trio Algarvio





#### Mass Fabricating









Steamship Pier, Homers Wharf, Leonard's Wharf









#### NBPA Pier 3







#### Global Fuels






#### **AGM Marine Contractors**








#### Popes Island Marina














#### North Terminal









#### Revere Copper





Kyler's Catch Seafood



# Project Schedule

- Synergies between three aspects of single project
- Schedule Drivers:
  - Ties to State's Capital Plan
  - Potential opportunities when CAD cell is ready to accept dredge materials
  - BUILD Grant schedule
- Delays could impact cost to private owners

CAD Cell

**Terminal** 

Phase V Dredging

Milestone	MONTH-YEAR
Design, Engineering, and Permitting Complete (CAD Cell)	September 2019
Start CAD Cell Construction (Top of CAD)	January 2020
Top of CAD Cell 100% Complete	April 2020
Start CAD Cell Construction (Bottom of CAD)	April 2020
CAD Cell 100% Complete (Bottom of CAD)	October 2020
Start Terminal Construction	Spring 2020
Design, Engineering, and Permitting Complete (Phase V)	July 2020
Start Phase V Dredging	November 2020
Berth Dredging 100% Complete	December 2021
Terminal Construction Complete	Winter 2021-2022


# Potential Waterfront Development Shoreline Facilities

- Eastern Fisheries
  - 1,000 LF solid fill bulkhead



# Potential Waterfront Development Shoreline Facilities


- Eastern Fisheries
  - Ex. area below pier is stone rip rap covered with sediment
  - Proposed bulkhead at fender line
  - Approximately 40,000 SF of proposed fill



Concept plan provided by AGM Marine

# Potential Waterfront Development Shoreline Facilities

- Sprague Site
  - 3 areas within this site




Maintaining navigational channels and depth is imperative for safe and efficient navigation by all port users and has a significant impact on daily operations for dozens of waterfront businesses.

This project ensures that the Port of New Bedford/Fairhaven remains a robust, full-service industrial working waterfront.


We thank you for your support of this important project!



## EPA Status update



## EPA Status update



## Thank you for support

- Senators Ed Markey & Elizabeth Warren
- Congressman Bill Keating
- Governor Charlie Baker & Lt. Governor Karyn Polito
- EOHED Secretary Mike Kennealy
- The New Bedford/Fairhaven Delegation, including: Senator Mark Montigny, Chairman Bill Straus, Antonio Cabral, Chris Markey, Paul Schmid, and Chris Hendricks
- Mayor Jon Mitchell & New Bedford Port Authority Commissioners Patricia Lareau, Richie Canastra, Jim Oliveira, Dr. Brian Rothschild, Davis Sullivan, Joseph Tavares
- New Bedford City Council Members Linda M. Morad, Joseph P. Lopes, Brian K. Gomes, Dennis Farias, Maria E. Giesta, Dana Ribeiro, Naomi R.A. Carney, Debora Coelho, Ian Abreu, Hugh Dunn, Scott J. Lima, William Brad Markey

